



Avaya Communication Server 1000

Communication Server 1000  
Chassis System Evaluation

Avaya Data Solutions  
Document Date: November 2010  
Document Number: NN43011-300  
Document Version: 05.02

© 2010 Avaya Inc.  
All Rights Reserved.

## Notices

While reasonable efforts have been made to ensure that the information in this document is complete and accurate at the time of printing, Avaya assumes no liability for any errors. Avaya reserves the right to make changes and corrections to the information in this document without the obligation to notify any person or organization of such changes.

## Documentation disclaimer

Avaya shall not be responsible for any modifications, additions, or deletions to the original published version of this documentation unless such modifications, additions, or deletions were performed by Avaya. End User agree to indemnify and hold harmless Avaya, Avaya's agents, servants and employees against all claims, lawsuits, demands and judgments arising out of, or in connection with, subsequent modifications, additions or deletions to this documentation, to the extent made by End User.

## Link disclaimer

Avaya is not responsible for the contents or reliability of any linked Web sites referenced within this site or documentation(s) provided by Avaya. Avaya is not responsible for the accuracy of any information, statement or content provided on these sites and does not necessarily endorse the products, services, or information described or offered within them. Avaya does not guarantee that these links will work all the time and has no control over the availability of the linked pages.

## Warranty

Avaya provides a limited warranty on this product. Refer to your sales agreement to establish the terms of the limited warranty. In addition, Avaya's standard warranty language, as well as information regarding support for this product, while under warranty, is available to Avaya customers and other parties through the Avaya Support Web site: <http://www.avaya.com/support>

**Please note that if you acquired the product from an authorized reseller, the warranty is provided to you by said reseller and not by Avaya.**

## Licenses

THE SOFTWARE LICENSE TERMS AVAILABLE ON THE AVAYA WEBSITE, [HTTP://SUPPORT.AVAYA.COM/LICENSEINFO/](http://SUPPORT.AVAYA.COM/LICENSEINFO/) ARE APPLICABLE TO ANYONE WHO DOWNLOADS, USES AND/OR INSTALLS AVAYA SOFTWARE, PURCHASED FROM AVAYA INC., ANY AVAYA AFFILIATE, OR AN AUTHORIZED AVAYA RESELLER (AS APPLICABLE) UNDER A COMMERCIAL AGREEMENT WITH AVAYA OR AN AUTHORIZED AVAYA RESELLER. UNLESS OTHERWISE AGREED TO BY AVAYA IN WRITING, AVAYA DOES NOT EXTEND THIS LICENSE IF THE SOFTWARE WAS OBTAINED FROM ANYONE OTHER THAN AVAYA, AN AVAYA AFFILIATE OR AN AVAYA AUTHORIZED RESELLER, AND AVAYA RESERVES THE RIGHT TO TAKE LEGAL ACTION AGAINST YOU AND ANYONE ELSE USING OR SELLING THE SOFTWARE WITHOUT A LICENSE. BY INSTALLING, DOWNLOADING OR USING THE SOFTWARE, OR AUTHORIZING OTHERS TO DO SO, YOU, ON BEHALF OF YOURSELF AND THE ENTITY FOR WHOM YOU ARE INSTALLING, DOWNLOADING OR USING THE SOFTWARE (HEREINAFTER REFERRED TO INTERCHANGEABLY AS "YOU" AND "END USER"), AGREE TO THESE TERMS AND CONDITIONS AND CREATE A BINDING CONTRACT BETWEEN YOU AND AVAYA INC. OR THE APPLICABLE AVAYA AFFILIATE ("AVAYA").

## Copyright

Except where expressly stated otherwise, no use should be made of the Documentation(s) and Product(s) provided by Avaya. All content in this documentation(s) and the product(s) provided by Avaya including the selection, arrangement and design of the content is owned either by Avaya or its licensors and is protected by copyright and other intellectual property laws including the sui generis rights relating to the protection of databases. You may not modify, copy, reproduce, republish, upload, post, transmit or distribute in any way any content, in whole or in part, including any code and software. Unauthorized reproduction, transmission, dissemination, storage, and or use without the express written consent of Avaya can be a criminal, as well as a civil offense under the applicable law.

## Third Party Components

Certain software programs or portions thereof included in the Product may contain software distributed under third party agreements ("Third Party Components"), which may contain terms that expand or limit rights to use certain portions of the Product ("Third Party Terms"). Information regarding distributed Linux OS source code (for those Products that have distributed the Linux OS source code), and identifying the copyright holders of the Third Party Components and the Third Party Terms that apply to them is available on the Avaya Support Web site: <http://support.avaya.com/Copyright>.

## Trademarks

*The trademarks, logos and service marks ("Marks") displayed in this site, the documentation(s) and product(s) provided by Avaya are the registered or unregistered Marks of Avaya, its affiliates, or other third parties. Users are not permitted to use such Marks without prior written consent from Avaya or such third party which may own the Mark. Nothing contained in this site, the documentation(s) and product(s) should be construed as granting, by implication, estoppel, or otherwise, any license or right in and to the Marks without the express written permission of Avaya or the applicable third party. Avaya is a registered trademark of Avaya Inc. All non-Avaya trademarks are the property of their respective owners.*

## Downloading documents

For the most current versions of documentation, see the Avaya Support. Web site: <http://www.avaya.com/support>

## Contact Avaya Support

Avaya provides a telephone number for you to use to report problems or to ask questions about your product. The support telephone number is 1-800-242-2121 in the United States. For additional support telephone numbers, see the Avaya Web site: <http://www.avaya.com/support>

## Table of Contents

<b>AVAYA COMMUNICATION SERVER 1000 CHASSIS/ MERIDIAN 1 PBX 11C CHASSIS SYSTEM EVALUATION</b> .....	<b>4</b>
LOCATION PROFILE .....	6
CS 1000 CHASSIS SAMPLE SITE LAYOUT .....	8
<b>SYSTEM AND SITE REQUIREMENTS CHECKLIST</b> .....	<b>14</b>
EQUIPMENT ROOM ENVIRONMENT .....	14
POWER AND GROUNDING .....	16
AC POWER & GROUND WORKSHEET .....	20
SYSTEM POWER AND GROUND CONNECTIONS .....	22
CHASSIS INSTALLATION .....	26
CHASSIS INSTALLATION .....	29
SYSTEM OPERATION .....	30
SYSTEM SOFTWARE .....	32
NETWORKING PARAMETERS FOR VOIP .....	34
PRODUCT BULLETINS FOR VINTAGE/RELEASE UPDATES .....	36

# Avaya Communication Server 1000 Chassis/ Meridian 1 PBX 11C Chassis System Evaluation

for

\_\_\_\_\_

**SUMMARY:**

A system evaluation of the \_\_\_\_\_ (Customer)  
Avaya Communication Server 1000 CHASSIS solution in  
\_\_\_\_\_ (City) was requested by  
\_\_\_\_\_ (Name) of  
\_\_\_\_\_ (Company). The evaluation was performed  
on \_\_\_\_\_ (Date). The nature of the evaluation was to determine if the  
Avaya CS 1000 CHASSIS was installed per manufacturing specifications and  
Product Bulletin requirements.

**DISTRIBUTION:**

**EVALUATED BY:**

**DATE:**

A stand-alone IP Trunk (ITG Trunk) configuration is the only IP application supported on the Meridian 1 Option 11C platform in Communication Server 1000 Release 5.5 or earlier.

Systems described within this document that are configured with IP Phones or Signaling Servers using Communication Server 1000 Release 4.5 and want to upgrade to Communication Server 1000 Release 7.5 must be upgraded to Avaya Communication Server 1000E with a Common Processor Pentium Mobile (CPPM) call processor. For migrations to Communication Server Release 7.5, refer to:

- *Avaya Communication Server 1000E Upgrade - Hardware Upgrade Procedures (NN43041-464)*
- *Avaya Communication Server 1000E Upgrade - Software Upgrades (NN43041-458)*

## Location Profile

### Site Information:

Audit Engineer:	_____	Evaluation Date:	_____
Distributor:	_____	Customer:	_____
Address:	_____	Address:	_____
Contact:	_____	Site Telephone:	_____
Telephone:	_____	Attendees:	_____
Email:	_____		_____


### System Information:

System Serial Number XXXXX

	Type/Platform	Software Release	Ports
PBX	<u>CS 1000 CHASSIS</u>	<u>XX21/X.00</u>	<u>XXX</u>
TM	_____	_____	_____
Call Center Server	_____	_____	_____
Call Pilot IPE	_____	_____	_____
VGMC	_____	_____	_____
Signaling Server (ISP 1100, CPPM, COTS)	_____	_____	_____



## CS 1000 Chassis Sample Site Layout



## FINDINGS AND RECOMMENDATIONS

**Introduction:**

The evaluation of this CS 1000 System Chassis, located \_\_\_\_\_  
 \_\_\_\_\_ was requested by \_\_\_\_\_. The request was initiated because \_\_\_\_\_.

The evaluation was performed on (date) \_\_\_\_\_ and covered the areas of Equipment Room Environment, Maintenance and Technician Area Environment, Power and Grounding, System Power and Ground Connections, Chassis Installation, Cabling Installation, System Operation, System Software, and Network Parameters for VoIP. \_\_\_\_\_ (name of company representative) was the main contact person during the evaluation process. All questions that pertain to this report may be directed to \_\_\_\_\_.

## DISCREPANCIES AND RECOMMENDATIONS:

### EQUIPMENT ROOM ENVIRONMENT

<p><b>Item #</b></p> <p><b>Findings:</b></p> <p><b>Recommendation:</b></p>	
----------------------------------------------------------------------------------	--

## MAINTENANCE AND TECHNICIAN AREA ENVIRONMENT

<b>Item #</b>	
<b>Findings:</b>	
<b>Recommendation:</b>	

## POWER AND GROUNDING

<b>Item #</b>	
<b>Findings:</b>	
<b>Recommendation:</b>	

## SYSTEM POWER AND GROUND CONNECTIONS

<b>Item #</b>	
<b>Findings:</b>	
<b>Recommendation:</b>	

## CHASSIS INSTALLATION

<b>Item #</b>  <b>Findings:</b>  <b>Recommendation:</b>	
---------------------------------------------------------------------	--

## CABLING INSTALLATION

<b>Item #</b>  <b>Findings:</b>  <b>Recommendation:</b>	
---------------------------------------------------------------------	--

## SYSTEM OPERATION

<b>Item #</b>	
<b>Findings:</b>	
<b>Recommendation:</b>	

## SYSTEM SOFTWARE

<b>Item #</b>	
<b>Findings:</b>	
<b>Recommendation:</b>	

## NETWORK PARAMETERS FOR VoIP

<p><b>Item #</b></p> <p><b>Findings:</b></p> <p><b>Recommendation:</b></p>	
----------------------------------------------------------------------------------	--

## CONCLUSION

**NOTE:** This report is based on checklist items contained in this document. The checklist item under each subheading is answered with a “Y” or “N”, signifying that it either complies or does not comply with Avaya specifications. An “N/A” means that the checklist question does not apply in this instance. The specifications are based on Avaya Practices, Product Bulletins, Product Advisories, and General Release Bulletins. Each checklist item is given a weight. The item may be deemed as “Critical, Major, Minor, or Recommended” in nature. A system evaluation is found to be “non-compliant” when one “Critical” or two “Major” discrepancies have been identified. Checklist weighting is not given to Applications products questions. The aim of an evaluation is to ensure installation completeness, optimize system performance/reliability, and provide a safe environment for personnel.

**Further Comments:**

## SYSTEM AND SITE REQUIREMENTS CHECKLIST

### Equipment Room Environment

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering* (NN43011-220)

*Meridian 1 Small System Installation and Commissioning* (NN43011-310)

1. Temperature is maintained between 0° and 45° C (32° and 113° F) and does not deviate any more than 5°F within a 24 hour period. A temperature of 22°C (72°F) is recommended.  
Temperature: \_\_\_\_\_°(Indicate C or F) [Major] \_\_\_\_\_
2. Humidity is between 5% and 95% non-condensing. Humidity \_\_\_\_\_%  
[Major, Critical if more than 95% or less than 5%] \_\_\_\_\_
3. Environment does not show any visible signs of moisture. [Critical] \_\_\_\_\_
4. Ventilating openings on equipment are free of obstructions. [Major] \_\_\_\_\_
5. The room is clean, relatively dust-free, and well ventilated.  
[Minor, Major if concrete dust] \_\_\_\_\_
6. Floor is sealed concrete, vinyl, raised floor (no dust or moisture) [Major] \_\_\_\_\_
7. Equipment location is not subject to constant vibration. [Major] \_\_\_\_\_
8. Equipment is located at least 12 ft (3660 mm) away from sources of electrostatic, electromagnetic, or radio frequency interference, such as power tools, appliances (such as vacuum cleaners), office business machines (such as copying machines), all electric motors, and electrical transformers. [FCC CFR 47 Part 15 for Class A devices. (<20 milliGauss ELF) [Major] \_\_\_\_\_
9. Equipment is not located under liquid-carrying pipes. [Major] \_\_\_\_\_
10. Equipment room is not conducive to generating electrostatic discharge (ESD) [Major] \_\_\_\_\_
11. Anti-static wrist straps, sprays and/or mats in evidence on site. [Recommendation] \_\_\_\_\_
12. Switch room door has a lock installed. [Minor] \_\_\_\_\_
13. No tripping or safety hazards exist in the equipment room. [Major] \_\_\_\_\_

## Equipment Room Environment

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

- 14. Lighting illumination is 50 to 75 foot candles measured 76 cm (30 in.) above the equipment room floor. [Recommendation]
- 15. Equipment room is protected from receiving direct sunlight. Direct sunlight is prevented from shining on electronic hardware, especially disk drives. [Major]
- 16. Adequate floor space has been made available to install equipment racks, patch panels, power systems (UPS) etc. [Major]
- 17. RS-232 terminal/communications devices should not exceed the 50 foot cable length limit unless line drivers are utilized. [Major]
- 18. The storage room for spare parts is secure. [Recommendation]
- 19. If it is not possible that the site maintain the environment of the storage area exactly the same as the environment of the operating equipment, stored materials are allowed time to adjust to the equipment room environment before using them. [Major]
- 20. The storage area is dust-free and away from high humidity and machinery such as electric motors of transformers. [Major]
- 21. Circuit cards which are not in use are stored in a protective antistatic bag. The storage area is dust-free and away from high humidity and machinery such as electric motors or transformers. [Major]
- 22. Chassis covers are installed. [Major]

## Maintenance and Technician Area Environment

- 23. A locking cabinet or storage area is in place for backup disks [Recommendation]
- 24. The area contains a table or desk terminal, printer, or equivalent device [Recommendation]
- 25. Maintenance workstation is equipped with a: [Major]
  - dial-up modem or connected to the network;
  - web browser;
  - operational maintenance telephone.

## Equipment Room Environment

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

26. Observations/Comments

## Power and Grounding

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

### Avaya Communication Server 1000 System Chassis AC Service Panel

1. The AC supply conductors are dedicated and uninterrupted from the building primary source or transformer to the PBX main AC service panel. (This does not apply to sub panels). [Major]
2. Verify that an Isolated Ground (IG) or ACEG conductor is installed from MGN/ X0 to an IG or ACEG bus in the AC panel serving the PBX equipment room. This point will become the single point ground reference for the PBX. [Critical]  
*Note: In some cases an AC panel may not be a requirement. Various UPS systems will establish the same intent and purpose as the panel IG/ACEG bus. The engineer performing the evaluation should research the application and determine its intent.*
3. The IG/ACEG conductor is sized per code. (NEC 250). Note: It is recommended that the ACEG conductor be the same size as the largest phase conductor. [Major]
4. The IG/ACEG conductor runs in the same raceway (conduit) as the phase and neutral conductors (NEC 250). [Major]
5. The IG/ACEG conductor is insulated, permanent, and continuous (no splices). (NEC 250) [Major]

## Power and Grounding

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

6. A dedicated AC panel is installed in the PBX room for the Avaya CS 1000 and associated equipment only. Circuits being served for purposes such as lighting, air conditioning, heating, generators, copiers, or motors from the CS 1000 service panel are not recommended.

Panel I.D.: \_\_\_\_\_ [Major]

7. Circuit breakers are identified/labeled at the AC service panel. (NEC 110-22) [Minor]

8. Ensure that all voltage and current levels recorded are within the defined limits. [Critical]

*Note: A licensed Electrician should obtain these results. See the AC Power/Ground Worksheet*

9. The workspace clearance around the AC service panel is 3 feet. (NEC 110-26) [Major]

10. All RS-232 ancillary devices connected to the system I/O circuit cards must be wired from the same AC panel as the PBX power supplies, with individual hot, neutral, and isolated/ACEG ground wires. [Critical]

*Note: Protection devices such as electro-optical isolators must be installed for all RS-232 devices (terminal, modem, etc.) not served from the same AC service panel as the CS 1000 system.*

11. Power from each outlet meets the input requirements of at least one System Chassis power supply as listed in the following tables. [Major]

AC input requirements for each NTDK91 Chassis and NTDK92 Chassis Expander		y/n
North America		
Voltage	Recommended: 100-120 volts Maximum limits: 90 and 132 volts Single phase	
Frequency	50-60 Hz	
Power (I/P max)	550 VA maximum	
Outlet Type	120 volt, 15 Amp supply	

## Power and Grounding

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

AC input requirements for each NTDK91 Chassis and NTDK92 Chassis Expander		y/n
<b>Europe and UK</b>		
<b>Voltage</b>	Recommended: 208/220 volts Maximum limits: 180 and 250 volts Single phase	
<b>Frequency</b>	50-60 Hz	
<b>Power (I/P max)</b>	550 VA maximum	
<b>Outlet Type</b>	208/240 volt, 15 Amp supply	
<i>Note: The supplied power must be single-phase 240 or three-phase 208 Y, and must have a system ground conductor.</i>		

AC input requirements for each NTDK91 Chassis and NTDK92 Chassis Expander		y/n
<b>Germany</b>		
<b>Voltage</b>	Recommended: 230 volts Maximum limits: 180 and 250 volts Single phase	
<b>Frequency</b>	50 Hz	
<b>Power (I/P max)</b>	550 VA maximum	
<b>Fuse</b>	16A	
<b>Outlet Type</b>	Receptacles by DIN regulation	

### Location of power outlets

**NOTE:** The maximum distance between a power outlet and the System Chassis is met in relation to the length of the power cord.

- In North America, the power cord is 9 ft 10 in. (3000 mm).
- Outside North America, the power cord is 8 ft 2 in. (2490 mm).

## Power and Grounding

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

12. Observations/Comments

## AC Power & Ground Worksheet

### AC Service Panel Measurements

*Note: If a portable UPS system is used, measurements will only be taken on the input/output voltage and the neutral-ground voltage. Percent of load must also be notated*

Voltage Measurements:	AC	MIN -MAX
Between neutral and phase A	_____ volts	105v 125v
Between neutral and phase B	_____ volts	105v 125v
Between neutral and phase C	_____ volts	105v 125v
Between ground and phase A	_____ volts	105v 125v
Between ground and phase B	_____ volts	105v 125v
Between ground and phase C	_____ volts	105v 125v
Between phase A and phase B	_____ volts	180v 250v
Between phase A and phase C	_____ volts	180v 250v
Between phase B and phase C	_____ volts	180v 250v
Between neutral and ground (ACEG)	_____ Vrms	0.0v 0.5Vrms
UPS percent of load:	_____	
UPS input voltage:	_____	
UPS output voltage:	_____	
<b>Current Measurements:</b>	<b>AC</b>	<b>MAX</b>
	_____	_____

Voltage Measurements:	AC	MIN -MAX
Neutral conductor amps	_____ amps	See Note 1
Ground conductor amps (IG or ACEG)	_____ amps	0.5 amps
Phase A amps	_____ amps	
Phase B amps	_____ amps	
Phase C amps	_____ amps	

Note 1: The neutral current should never exceed the current in any single-phase leg.

A licensed electrician must take AC service panel measurements.

Voltage and current values must comply with documents.

Voltage between neutral and ground could signify poor or loose connections or non-continuous grounding.

Current flow in the grounding conductor may indicate that the neutral has been used for equipment grounding.

If currents are balanced in a three phase system and there is significant neutral current, then harmonics are present. Harmonics can deteriorate transformers over time by over heating their internal wiring. Solution: Use transformers specifically designed for harmonic loading (k-factor-rated).

## System Power and Ground Connections

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering* (NN43011-220)

*Meridian 1 Small System Installation and Commissioning* (NN43011-310)

1. If other data communications equipment is in the same rack/equipment cabinet as the Small System, each piece of equipment is powered from a grounded outlet. The same service panel services all outlets. [Major] 

---
  
2. The Signaling Server power cord is plugged into the rack's AC outlet and the rack's AC outlet is grounded to its dedicated electrical panel. [Major] 

---
  
3. In an installation where a dedicated panel cannot provide optimal conditions, an load isolation transformer or load isolation transformer-based UPS/Line conditioner with the following characteristics is used:  
[Major]
  - 120/208/240 V AC input, over-current protected at primary 

---
  - 120/208/240 V AC available at secondary outputs, each circuit breaker protected 

---
  - primary and secondary windings are completely isolated from one another 

---
  - it is approved for use locally as a stand-alone user product (CSA, UL, or other locally recognized clear markings) 

---
  - it is capable of providing power to all CS 1000 components operating at the same time at full load 

---
  - equipment unrelated to the CS 1000 is not powered from a transformer that provides service to the CS 1000 system 

---
  - it is electrostatically shielded to minimize ELF fields 

---
  
4. The method of grounding used for Small Systems depends on whether the same service panel powers all chassis. This installation uses one of the following grounding scenarios: [Major]
 

In System Chassis with one or more chassis powered by one service panel:

For each system chassis, a #6 AWG (#40 Metric Wire Gauge) ground wire is connected from the chassis to the NTBK80 grounding block. The grounding block is connected to a ground source (the ground bus in the AC power service panel). The chassis and the chassis expander are considered as the same ground. The ground wire is jumped from the chassis expander to the chassis and then back to the grounding block.

---

## System Power and Ground Connections

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

System Chassis with more than one chassis, powered by different service panels:

For each chassis, a #6 AWG (#40 Metric Wire Gauge) ground wire is connected from the chassis to the NTBK80 grounding block. If any chassis cannot be powered from the same service panel, it is ground separately from the other chassis back to the service panel that supplies it. Each chassis and chassis expander pair is powered from the same service panel.

**Note 1:** If a chassis requires a separate ground, it is grounded using the same method used for a system with one chassis.

**Note 2:** In the UK, you can connect the grounding wire from the chassis to an NTBK80 grounding block or through a Krone Test Jack Frame.

Grounding multiple pieces of equipment in a rack/equipment

Cabinet:

Each piece of equipment in a rack/equipment cabinet is grounded. If a piece of equipment does not have a ground lug, then the whole rack/equipment cabinet is grounded.

5. The installation meets the specific grounding requirements for the area:

[Major]

Germany	#8 AWG (10 mm <sup>2</sup> ) green/yellow wire
North America; other areas in Europe	Not smaller than #6 AWG (16 mm <sup>2</sup> ) at any point
UK	Two green/yellow wires no thinner than two 10 mm <sup>2</sup>

6. A system ground conductor, sized at a minimum of a #6 AWG stranded, insulated wire is installed from the chassis ground bus to the ACEG bus in the AC panel. Where UPS systems are employed, a #6 AWG wire can be installed from the chassis ground bus to the grounded metallic case of the UPS using a ground lug. [Critical if missing; Major if undersized].

7. A #6 AWG insulated, stranded conductor is installed between each CS 1000 chassis ground lug and the cabinet ground bus. [Major]



## System Power and Ground Connections

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

### Ancillary Equipment Power

20. Power for system equipment in the switch room is: [Major]
- powered from the same panel or transformer as the Small System
  - grounded to the same panel or transformer as the Small System
21. Service receptacles for AC-powered Small Systems and related equipment are: [Major]
- rated for 120 or 240 V, 15 or 20A, 50-60 Hz, 3-pole, 3-wire, grounded
  - grounded to the same location so as to form a SPG

### Other items

22. QUA6 Power Failure Transfer Units (PFTU) are available to transfer trunk lines during a power or system failure. [Recommendation]

**Note:** The appropriate AC power cord kit is used for the installation as listed in the following table. (These cords connect a CS 1000 System Chassis to a commercial AC power source.)

Country / Region	AC Power Cord	Voltage Rating	Current Rating	Plug Type
North America	A0379412	250 V	10 A	NEMA 6-15P
Argentina	A0814961	250 V	10 A	IRAM 2073
North America	NTTK14	125 V	13 A	NEMA 5-15P

Country / Region	AC Power Cord	Voltage Rating	Current Rating	Plug Type
Australia/ New Zealand	NTTK15	250 V	10 A	AS3112
Europe	NTTK16	250 V	10 A	CEE(7)VII
Switzerland	NTTK17	250 V	10 A	SEV 1011
UK/Ireland	NTTK18	250 V	10 A	BS1363
Denmark	NTTK22	250 V	10 A	AFSNIT

## Chassis Installation

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

1. The Meridian 1 PBX 11C Chassis is installed either vertically or horizontally on a wall, or is installed in a rack/cabinet. The mounting surface can support at least 100 lb (45 kg). [Major] 

---
2. Installations combining Small Systems meet the following minimum standards: [Major]
  - horizontal installations: 10 inches of free space on either side of the chassis. 

---
  - vertical installations: 12 inches of free space on the card side and 6 inches of free space on the cable side of the chassis. 

---
3. Installations with multi-chassis systems adhere to the following guidelines (for both horizontal and vertical expansion): [Major]
  - The maximum distance between the Main Chassis and each fiber Expansion Chassis is 1.8 mi (3 km) 

---
  - The minimum distance between the Main Chassis and the chassis expander, when mounted above one another (vertical expansion), is 4 in. (102 mm). 

---



## Chassis Installation

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

## Chassis Cabling

- |     |                                                                                                                                                                                                 |       |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 6.  | Cabling must be installed in a neat and orderly fashion. [Major]                                                                                                                                | _____ |
| 7.  | MDF cables are seated and secured in place using factory velcro straps. [Major]                                                                                                                 | _____ |
| 8.  | All cables for chassis and Signaling Servers (SDI, AUX, VGMC ELAN/TLAN, CE-MUX, DS-30X, and 10/100BaseT cables) and adapters are properly fastened. [Major]                                     | _____ |
| 9.  | Power wiring must not be installed in a parallel fashion with CAT5 cabling. Installing power wires perpendicular to CAT5 cables is preferred and minimizes effects from EMI/ELF fields. [Major] | _____ |
| 10. | EMI mitigating ferrite rings (NTVQ83AA) are installed on Voice Gateway Media Card TLAN/ELAN patch cables. [Major]                                                                               | _____ |
| 11. | NTCW84JA assemblies are used for each VGMC connector. [Major]                                                                                                                                   | _____ |
| 12. | CAT5 patch cables are not installed near fluorescent lighting fixtures. [Major]                                                                                                                 | _____ |
| 13. | ELAN/TLAN patch cables for VGMC and Signaling Server hardware are "factory made" and kept at 20 feet or less. [Recommendation]                                                                  | _____ |
| 14. | All patch cables are labeled and correlate to a network infrastructure diagram/schematic. [Minor]                                                                                               | _____ |

## Chassis Installation

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

### Cross-connect terminal requirements

15. To allow for future expansion and equipment changes at the cross-connect terminal, the cross-connect terminal has enough space for connecting blocks to terminate the following wires:

[Recommendation]

- five 25-pair cables from each chassis
- four 25-pair cables from the chassis expander
- four conductors for the AUX cable from the chassis
- one 25-pair cable from each QUA6 Power Failure Transfer Unit (PFTU)
- wiring from telephone sets and trunks

---

---

---

---

---

---

16. The BIX cross-connect system is recommended for use with the Small System. However, use of this system is not mandatory. Some other cross-connect systems may be used (for example, the Krone Test Jack Frame for the UK and the Reichle Masari cross-connect terminal for Germany).

In the UK

If the Krone Test Jack Frame is used, only authorized personnel are allowed access the Krone Test Jack Frame and it is installed in a locked room or in an environment that prevents free access to the equipment. Refer to NN43011-310 Meridian 1 Small System Installation and Commissioning for additional information about the cross-connect terminals. [Major]

---

17. Observations/Comments

## System Operation

X11 Software General Release Bulletin (shipped with new software)

Meets  
Specifications  
Y / N

## System Diagnostics

- |     |                                                                                                                                                                                           |       |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 1.  | LD 30 Network and Signaling Diagnostic (NWS). [Minor]                                                                                                                                     | _____ |
| 2.  | LD 34 Tone and Digit Switch and Digitone Receiver (TDS). [Major] <i>Check results from the midnight routines.</i>                                                                         | _____ |
| 3.  | LD 37 Input/Output Diagnostic (IOD). <i>Use "STAT" command for TTYs.</i> [Major]                                                                                                          | _____ |
| 4.  | LD 38 Conference Circuit Diagnostic (CNF) [Major] <i>Check results from the midnight routines.</i>                                                                                        | _____ |
| 5.  | LD 43 Data Dump (EDD). [Critical] Check for successful completion of a manual data dump.                                                                                                  | _____ |
| 6.  | LD 44 Software Audit (AUD). [Major] <i>Must be configured in BKGD of Ld-17. Check for normal AUD000 messages.</i>                                                                         | _____ |
| 7.  | LD 48 Status of ELAN/ Mail/ESDI Links. [Major] <i>Make sure all AMLs that are in use are ACTIVE EMPTY.</i>                                                                                | _____ |
| 8.  | LD 60 Digital Trunk Diagnostic (DTI/PRI). [Major] <i>Use the SSCK command to check system clocks. Also check midnight routines for frame slips, CRC errors.</i>                           | _____ |
| 9.  | GTR, documentation, and Backup logs are located in switch room. <i>Note: Ensure appropriate level and system type of documents are available.</i> [Minor]                                 | _____ |
| 10. | The PBX maintenance modem/terminal server performs as expected. [Major]                                                                                                                   | _____ |
| 11. | The system is equipped with a working maintenance terminal and printer. [Major]                                                                                                           | _____ |
| 12. | A PC is available on location in order to access Element Manager [Major]                                                                                                                  | _____ |
| 13. | Minimum level PEPs are installed in the system. This includes DepList PEPs for the call servers, required PEPs for Signaling Servers, and Voice Gateway Media Card PEPs. [Recommendation] | _____ |

## System Operation

Meets  
Specifications  
Y / N

X11 Software General Release Bulletin (shipped with new software)

- 14. The system is equipped with a working maintenance terminal and printer. [Major]
- 15. A PC is available on location in order to access Element Manager/NRS [Major]
- 16. Minimum level PEPs are installed in the system. This includes DepList PEPs for the Call Servers, required PEPs for Signaling Servers, and Voice Gateway Media Card PEPs. [Recommendation]
- 17. IP sets are on the latest recommended firmware. [Recommendation]
- 18. Signaling Servers are load sharing (equal number of registered IP phones) [Recommendation]
- 19. Printouts of Signaling Server config.ini and bootp.tab files readily available. [Minor]  
  
pdt> cd /u/config, copy config.ini, copy bootp.tab

## Memory size

- 20. The installation meets the minimum memory requirements for CS 1000 Release 5.5 software. [Major]

Avaya Communication Server 1000M Release 5.5 memory requirements			
Processor	Flash memory required	DRAM memory required	Total memory
SSC	64 MByte	32 MByte	96 MByte

## System Operation

Meets  
Specifications  
Y / N

---

X11 Software General Release Bulletin (shipped with new software)

- 21. The installation does not exceed the maximum call register count recommended for CS 1000M Release 5.5 software. [Major]

Recommended maximum call register counts			
	Recommended	Memory	Memory
	call register	required	required
System	count	(SL-1 words)	(MByte)
CS 1000	800	181 600	0.693
<b>Note: Call registers are 227 SL-1 words long. One SL-1 word is 4 bytes.</b>			

- 22. Observations/Comments

## System Software

Meets  
Specifications  
Y / N

### Overlay 15/21 Customer Data Block

- 1. SRCD (Auto Set Relocation Code) has a value programmed (0000 is Okay). [Major if SPRE is 1, Minor if other]

---

## System Software

Meets  
Specifications  
Y / N

---

### Overlay 17/22 Configuration Record

2. Daily Routine defined as LD 34, 38, 60,137 [Major]

---

3. LD 44 in background routine. [Major]

---

4. The number of call registers (NCR) within the maximum value required per GRB documentation regarding port size and features used.

**CS 1000M- 800 call registers** [Major]

---

5. 1000M LPIB and HPIB values equal 450 [Recommendation]

---

6. History File is defined as MTC, BUG and is set at minimum length of 60,000 characters. [Major]

---

7. ERRM is configured as ERR, BUG, AUD [Major]

---

8. 1.1.1 RLS IDs are configured for each D-Channel where appropriate. [Major]

---

### Overlay 11/12/13 Digital Sets / Attendant Consoles/ Digitone Receivers

9. Switchroom phone requires MTA for class of service. [Major]

---

10. Consoles powered via unused TNs are correctly programmed “PWR”. [Major]

---

11. Consoles are cross-wired properly and must utilize consecutive units. [Major]

---

## System Software

Meets  
Specifications  
Y / N

---

12. Observations/Comments

## Networking Parameters for VoIP

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

1. A LAN/WAN assessment has been performed on the customer network. [Critical]
2. The layer 2 switch ports (Baystack 470) in place for the CS 1000 ELAN/TLAN are configured for full duplex, auto negotiate. [Major]
3. The port speed for ELAN related ports are configured at 10 Mbps for CS 1000M systems. [Major]
4. The ELAN subnet and the TLAN subnet are on separate subnets. [Major]
5. All applications on the ELAN subnet are on the same subnet. [Major]
6. The port speed for all TLAN ports on the layer 2 switch are configured for 100 Mbps. [Major]

---



---



---



---



---



---

## Networking Parameters for VoIP

Meets  
Specifications  
Y / N

For additional information refer to:

*Meridian 1 Small System Planning and Engineering (NN43011-220)*

*Meridian 1 Small System Installation and Commissioning (NN43011-310)*

- 7. VGMC circuit cards in the same node are on the same TLAN subnet. [Major] \_\_\_\_\_
  
- 8. Minimum of one VGMC DSP resource for every TDM port (T-1 trunks, digital phones, analog phones, analog trunks, Avaya CallPilot channels). \_\_\_\_\_  
 [Recommendation]
 

*For non-blocking requirements one DSP per TDM port is a best practice.*

\_\_\_\_\_
  
- 9. Layer 2 switches derive UPS power from different branch circuit sources, if possible, in order to minimize single points of failure. [Recommendation] \_\_\_\_\_
  
- 10. Signaling Server (ISP 1100, CPPM, COTS) \_\_\_\_\_
  
- 11. Observations/Comments \_\_\_\_\_

=

